SR NO.	NAME OF ITEM	Description	QUANTITY	UNIT	RATE	per	amount in rupees
1	Excavation	Earthwork excavation in open cutting upto 5'-0" (1.5 m) 17.1 to depth for storm water channels, drains, sullage drains in 17.5 open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead:-	935.516	cft	7,623.55	1000 cft	7128.01925

2	Concrete	Cement concrete plain including placing, 20.1 compacting, finishing and curing complete (including screening and washing of stone aggregate):	915.34	cft	22977.75	100cft	210324.5369
3	Brickwork	Pacca brick work in foundation and plinth in:- (cement, sand mortar(1:4))	1065.228	cft	27027.5	100cft	287904.4977
4	paint exterior coat 2	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	1520.21	sft	960.85	100sft	14606.93779
5	paint exterior coat 1	Providing and applying weather shield paint of approved quality on external surface of building including preparation of	1520.21	sft	1957.4	100sft	29756.59054

		surface, application of primer complete in all respect:					
6	Brick work	Pacca brick work in ground floor:-i) cement, sand mortar:-	1402.532	cft	23707.6	100cft	332506.6764
7	paint interior coat 2	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	3249.21	sft	446.15	100sft	1990.498225
8	paint interior coat 1	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	3249.21	sft	865.5	100sft	28121.91255

9	Wood work	First class teak wood wrought joinery in doors and windows, etc. paneled, paneled and glazed or fully to glazed and fixed in position, including chowkat, holdfast, tower bolt, chocks, rubber stop, cleats/G.I. clamps, & chords with hooks, nails, screws, etc. complete (excluding sliding bolt and lock):-	119	square ft	3774	sft	449106
10	Glasswork+Aluminium	Providing and fitting all types of glazed aluminum windows of anodized bronze color partly fixed and partly sliding using deluxe sections of approved manufacturer having frame size of 100 x 20 mm (4"x¾") and leaf	115.83	square ft	477	sft	55250.91

		frame sections of 50 x 20 mm (2"x¾"), all of 1.6mm thickness including 5 mm thick imported tinted glass with rubber gasket using approved standard latches, hardware c., as approved by the Engineer in-charge.					
11	plaster	Cement plaster 1:4 upto 20' (6.00 m) height:- ½" (13 mm) thick	4356.69	sft	2153.8	100 sft	93834.38922
12	Steel	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labor charges for binding of steel reinforcement (also includes removal of rust from	4165.61	lb.	8090.45	cwt=112lb	300907.6734

		bars):-) Deformed bars (Grade-40)					
13	Marble	Providing and laying floor of mosaic marble chips tiles 1"(25 mm) thick of approved quality and shade, laid in white cement and pigment, over ¾"(20 mm) thick bedding of cement sand mortar 1:2, including finishing and polishing, complete	903.072	sft	9,226.45	100sft	83321.48654
14	Tiles	Cement concrete tiles laid in 1:2 cement mortar, over 3/4" (20 mm) thick bed of cement mortar 1:2:-a:) 12"x12"x1" (300 x 300 x 25 mm)	283.2	sft	4,971.35	100sft	14078.8632
15	D.P.C	Providing and laying damp proof course of cement concrete 1:2: 4(using	11.82666667	sft	5112.35	sft	60462.05933

		cement, sand and shingle), including bitumen coating :- 1½" thick (40 mm)					
16	Backfilling	Earthwork excavation in open cutting upto 5'-0" (1.5 m) 17.1 to depth for storm water channels, drains, sullage drains in 17.5 open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead:-	149.712	cft	7,623.55	1000cft	1141.336918

17	skirting tiles	Tile skirting laid in 1:2 cement mortar, over ¾"(20 mm) thick cement mortar, 1:2 including cement washing and filling joints complete:-	78.5614	sft	12,287.25	100sft	9653.035622
18	Pacca Brick Work in Roof (cement, sand mortar(1:4))	Pacca Brick Work in Roof (cement, sand mortar(1:4)) Add extra labor on item No. 5 for brickwork in:-	36.6273	cft	24668.05	100cft	9035.240678
19	Main gate	Making and fixing steel grated door with 1/16" thick (1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm) center to center, with locking arrangement.	48	sft	1251.95	per sft	60093.6
20	Two coats of bitumen	Two coats of bitumen laid hot using 34 lbs. per %Sft, or 1.72 Kg per square	903.05597	sft	2137.7	100sft	19304.62747

		meter over roof and blinded with sand at one Cft. per %Sft. (0.003 cu.m per sq.m)					
21	Two layers of Polythen sheet	Providing and Laying Insulation material of Extruded Polystyrene XPS in Rigid Insulation / Foam Board on roof or walls, Density 32-38Kg/M, compressive strength 250-400 kpa, R-value 5 per inch thickness and water absorption (1% by volume, cell structure clored cell) i/c cutting and placing in position. complete in all respect.	903.05597	sft	10865.9	100sft	98125.15864
22	Well compacted earth	Earth flooring, consisting of 6"(150 mm) thick consolidated layer of moistened earth, including ramming.	2108.78	cft	3516.5	1000cft	7415.52487

23	6" Sand filling	Supplying and filling sand under floor; or plugging in wells	490.53	cft	2103.15	100Cft	10316.5817

Total 2184386.157