Estimating in Building Construction

Chapter 17 Electrical

Electrical

- Often governed by the National Electrical Code
- Usually subcontracted out
- Closer cooperation between general contractor and the electrical contractor because the conduits and fixtures must be cast in the concrete

Includes

- Wiring (rough work)
- Conduit
- Transformers
- Switches
- Lighting Panel
- Fixtures (Finish work)
- Breakers
- Weatherproof Outlets
- Control panels
- Temporary wiring

Coordination Requirements

- Underground utilities
  - Location, size, excavation by whom, from where?
- Equipment
  - Recessed depth, size of access openings, method of feed, supports, by whom, size limitations.

Coordination Requirements

- Distribution
  - Outlet locations, materials, method of feed, in walls, under floor, overhead, special considerations.
- Terminal fixtures and devices
  - Location, method of support, finish, color, and material.

Coordination Requirements

- Mounting
  - Mounting surface? Can it work?
- Specialty equipment
  - Field provisions, storage.

Coordination Requirements

- Scheduling
  - Work to be done? When required? Job to be completed on time, by who, why, when?

Thank You